



**VOGEL**  
S Y S T E M S

Method Statement

**THERMO DRY**

**PAINTING WORKS**

# **Table of Contents**

---

- 1. Scope
- 2. Purpose
- 3. Specifications clauses
- 4. Materials
- 5. Tools & equipment
- 6. Construction procedure
- 7. Risks
- 8. Health & safety
- 9. Storage
- 10. Quality control procedure
  - 10.1 general
  - 10.2 procedure

## SCOPE

The aim of this method statement is to provide and maintain effective quality control procedures and to execute the work in compliance to standard and good practice at all stages during the execution of Thermo dry painting works on the project site .



Application of Thermo dry painting works.

## PURPOSE

The purpose of this method statement is intended to inform the consulting engineer how the work will be delivered on site associated with risks and precautions to be taken during working on site.

The purpose of this statement:

- To outline how the work will be achieved on site.
- To meet the drawings and specifications requirements.
- To predict possible problems.

## SPECIFICATIONS CLAUSES

- Project specification.
- Approved shop drawing.
- Contract documents.

## MATERIALS

- Bonding primer
- VogaThermo-Dry
- Non-woven geotextile



**BONDING PRIMER**



**VOGATHERMO-DRY**

## TOOLS & EQUIPMENT

- Paint Brushes/ Rollers



- Grinder



- Paint Sprayers



AS REQUIRED.

- Hand Tools



Trowel , Spatula or putty knife ,scraper ,hammer ..etc).

- Air compressor



AS REQUIRED.

# CONSTRUCTION PROCEDURES

## Thermopainting for basement

1. Make sure that the reinforced concrete slab on the ground surface is dry, and the moisture content should be less than 5%

2. The surface must be roughened using a grinding machine or vacuum.

3. The prepared substrate should then be primed with (Bonding primer) from (Vogel) to achieve a chemical bonding between substrate and acrylic layer with consumption rate 0.1-0.15 kg/m<sup>2</sup>.

4. Apply a 1st putty coat where it is needed.

5. After drying of putty, apply the 1st coat of (VogaThermo Dry) water base, acrylic waterproofing coating from (Vogel) using a good quality roller (colour upon request) with consumption rate 1 kg/kg/coat.

6. Apply non-woven geotextile sheets 100:120 gm in density. Apply a 2nd perpendicular coat (VogaThermo Dry) from (Vogel) using a good quality roller (colour upon request) with consumption rate 1 kg/m<sup>2</sup>/coat.

7. After first coat being completely dry. Apply final coat from (VogaThermo Dry) from (Vogel) with low consumption than other coats 0.5 kg/m<sup>2</sup>/coat until be sure that the system is fully completed.




Dry surface



Grinding or vacuuming



Acrylic waterproofing



non-woven geotextile



**BONDING PRIMER**



**VOGATHERMO-DRY**



## RISKS

- Avoid any inhalation of vapours, avoid skin contact! Wear protective gloves and protective goggles! In case of skin contact, rinse immediately with soap and water! In case of eye contact, bathe eyes with water at once, then consult a doctor! Observe the guidelines concerning the handling of epoxy resins and amines issued by the Employer's Liability Insurance Associations.
- As with all chemical products, care should be taken, during use and storage, to avoid contact with eyes, mouth, skin and foodstuffs (which can also be tainted with vapour until product has fully cured or dried). Treat splashes to eyes and skin immediately. If accidentally ingested, seek medical attention. Re-seal containers after use..



## HEALTH AND SAFETY

- Make sure that the workers involved in the installation of the epoxy resin floor coating are experienced and well trained.
- Every stage of the installation must be supervised properly. Check all the routes of material transportation and remove any form of obstacle that could cause accidents. There should be frequent cleaning during working hours.
- Every equipment used must be maintained in accordance with legal requirements.
- Electrical connections should be handled by qualified and approved electricians.
- The workplace must be barricaded and well protected to prevent unauthorized personnel. A work permit must be issued to every person by the main contractor before work starts on the site.
- Appropriate loading and offloading equipment should be provided by the contractor. All the equipment should be certified and handled by a qualified operator.
- Keep a material safety data sheet to ensure that materials are handled well especially chemicals. Major spill kit available and personal protective equipment must be made available to every personnel must be worn at all times.



## STORAGE

---

- Store in dry conditions in the original packs. If stored at high temperatures and/or high humidity conditions the shelf life may be reduced. Materials should be protected from frost.
- Make sure all the pads have the same temperature during the entire installation period. Lay down the pads 24 hours before the installation to allow them to get their original dimensions. Install all the pads in a single laying session in order to guarantee installation under similar conditions

## CONTACT INFORMATION

---

 +201208160230

 [info@vogelsystems-eg.com](mailto:info@vogelsystems-eg.com)

 [vogelsystems-eg.com](http://vogelsystems-eg.com)